

Address of Work to be Done at: 17851 40<sup>th</sup> Ave Unit 200

Scope of Work: Fence Installation

Installing 333 Lf of 8' High NON - Climb Fence/Spear Top (Iron). Fence to be installed around building, 4' single swing gates with panic hardware to be installed at ea. building doorway for fire exit, 12' double drive gate. The gate is for access to future generator. 20' Double Drive Gates (One to small parking lot, One at dock) Fencing at dock to be plated on top off existing concrete wall.